### Automatic Transfer Switch Controller

# KOHLER. Power Systems

### Decision-Maker® MPAC 1500







Model KBS with Decision-Maker® MPAC 1500 Controller

### **Applicable Models**

Model	Description	
KCS	Standard-Transition Any Breaker ATS ‡	
KCP	Programmed-Transition Any Breaker ATS ‡	
KCC	Closed-Transition Any Breaker ATS §	
KBS	Standard-Transition Bypass/Isolation ATS §	
KBP	Programmed-Transition Bypass/Isolation ATS §	
KBC	Closed-Transition Bypass/Isolation ATS §	
KGS	Standard-Transition Bypass/Isolation ATS §	
KGP	KGP Programmed-Transition Bypass/Isolation ATS §	
KEP	KEP Service Entrance ATS §	
‡ Availab	* Available with automatic or non-automatic controller	
§ Available with automatic controller only		

## Decision-Maker<sup>®</sup> MPAC 1500 Controller Standard Features

- Microprocessor-based controller
- Environmentally sealed user interface
- LCD display, 4 lines x 20 characters, backlit
- Dynamic function keypad with tactile feedback pushbuttons allows complete programming and viewing capability at the door
- LED indicators: Source available, transfer switch position, service required (fault), and not in auto
- Broadrange voltage sensing (208-600 VAC) on all phases
- Phase-to-phase sensing and monitoring with 0.5% accuracy on both sources
- Frequency sensing with 0.5% accuracy on both sources
- Anti-single phasing protection
- Phase rotation sensing for three-phase systems
- Real-time clock with automatic adjust for daylight saving time and leap year
- Run time clock and operation counter
- Time-stamped event log
- Fail-safe transfer for loaded test and exercise functions
- DIP switches: password disable and maintenance
- Isolated RS-485 ports for Modbus connections (9.6, 19.2, and 57.6 kbps)
- Standard Ethernet communications with RJ45 connector for 10/100 ethernet connection
- Modbus® RTU and Modbus® TCP/IP protocols (Modbus® register map available)
- USB port. Connect a personal computer and use Kohler<sup>®</sup> SiteTech<sup>™</sup> software to view events and adjust settings \*
- Available in automatic and non-automatic versions; see supervised transfer control switch on page 5

### Programmable Features

- Programming and monitoring methods:
  - Monitoring and password-protected programming at the door using the keypad and display
  - Program using a PC with Kohler SiteTech software \*
- Over/undervoltage and over/underfrequency for all phases of the normal and emergency sources
- Adjustable time delays
- Load/no load/auto-load test and load/no-load exercise functions
- Programmable inputs and outputs
- Load bank control for exercise or test
- Time-based and current-based† load control, nine individual time delays for selected loads
- In-phase monitor (3-phase only)
- Password protection, three security levels
- \* SiteTech software is available to Kohler-authorized distributors and dealers.
- † Requires current sensing kit.

Modbus is a registered trademark of Schneider Electric.

### **Decision-Maker® MPAC 1500 Controller Features**

### **User Interface LED Indicators**

- Contactor position: source N and source E
- Source available: source N and source E
- Service required (fault indication)
- Not in automatic mode

### LCD Display

- System status
- Line-to-line voltage
- Line-to-neutral voltage
- Active time delays
- Source frequency
- Preferred source selection
- System settings
- Common alarms
- Load current, each phase (current sensing kit required)
- Inputs and outputs
- Faults
- Time/date
- Address
- Event history
- Maintenance records
- Exerciser schedule
- Exerciser mode
- Time remaining on active exercise

### **Dynamic Function Tactile Keypad Operations**

- Scroll up/down/forward/back
- Increase/decrease/save settings
- End time delay
- Start/end test or exercise
- Reset fault
- Lamp test

### **DIP Switches**

- Maintenance mode
- Password disable

### **Event History**

- View time and date-stamped events on the display or on a personal computer equipped with Kohler<sup>®</sup> SiteTech<sup>™</sup> software. \*
- Download complete event history files using Kohler SiteTech software and a PC connected to the USB port. \*

### Main Logic Board Inputs and Outputs

- Two (2) programmable inputs
- Two (2) programmable outputs
- \* SiteTech software is available to Kohler-authorized distributors and dealers.
- System parameters are factory-set per order. Modbus is a registered trademark of Schneider Electric.

### Communications

- Ethernet communications with RJ-45 connector for 10/100 ethernet connection
- Isolated RS-485 ports for Modbus communications
- Modbus<sup>®</sup> RTU and Modbus<sup>®</sup> TCP/IP protocols (Modbus<sup>®</sup> register map available)
- USB Port. Use SiteTech software to upload or download files and adjust transfer switch settings \*
  - Application software
  - Event history files
  - Language files
  - Parameter settings
  - Usage reports
  - Feature configuration

#### **Programmable Features**

- System voltage, 208-600 VAC †
- System frequency, 50/60 Hz †
- Single/three-phase operation †
- Standard/programmed/closed-transition operation †
- Bypass/isolation enable/disable \*
- Service entrance enable/disable †
- Preferred source selection allows the normal or emergency source to be used when both sources are available (alarm module required)
- Phase rotation: ABC/BAC/none selection with error detection
- Voltage and frequency pickup and dropout settings
- Voltage unbalance, enable/disable
- In-phase monitor: enable/disable and phase angle
- Transfer commit/no commit
- Source/source mode: utility/gen, gen/gen, utility/utility, or utility/gen/gen for 3-source systems
- Passwords, system and test
- Three-source system setup allows the use of one utility source and two generator sets
- Time, date, automatic daylight saving time enable/disable
- Time delays (see table)
- Exerciser: calendar mode, loaded/unloaded up to 21 events
- Test: loaded/unloaded/auto load (1-60 minutes)
- Remote test: loaded/unloaded
- Automatic override on generator failure (loaded test and exercise)
- Peak shave delay enable/disable
- Current monitoring (current sensing kit required)
- Load control pre/post-transfer delays, 9 individual time delays for selected loads
- Current-based load control settings: high/low current levels and load add/remove priority for 9 separate loads (current sensing kit required)
- Prime power sequence alternates between two generator sets with adjustable generator set runtimes
- Resettable historical data

### Decision-Maker® MPAC 1500 Controller Features, Continued

### **Programmable Inputs**

- Bypass contactor disable (for bypass/isolation switches)
- Forced transfer to OFF (programmed-transition models only; requires load shed accessory)
- Inhibit transfer
- Low battery voltage (external battery supply module required)
- Peak shave/area protection input
- Remote common fault
- Remote test
- · Remote end time delay
- Remotely monitored inputs, four (4) available
- Service disconnect (for service entrance models)
- Three-source system disable

#### **Programmable Outputs**

- Alarm silenced
- Audible alarm
- Chicago alarm control
- Common alarm events
- Contactor position
- Exercise active
- Fail to open, source 1/source 2 (service entrance models)
- Fail to close, source 1/source 2 (service entrance models)
- Failure to acquire preferred source
- Failure to acquire standby source
- Failure to transfer
- · Generator engine start, source N and E
- I/O module faults
- In-phase monitor synch
- Load bank control
- Load control active (pre/post transfer delay, up to 9 outputs)
- Loss of phase fault, source N and E
- Low battery fault (external battery supply module required)
- Maintenance mode
- Non-emergency transfer
- Not in automatic mode
- Over/underfrequency faults, source N and E (generator)
- Over/undervoltage faults, source N and E
- Peak shave/area protection active
- Phase rotation error, source N and E
- Preferred source supplying load
- Software-controlled relay outputs (four maximum)
- Source available, preferred and standby
- Standby source supplying load
- Test active
- Three-source system disable
- Transfer switch auxiliary contact fault
- Transfer switch auxiliary contact open
- Voltage unbalance, source N and E

Voltage and Frequency Sensing			
Parameter	Default	Adjustment Range	
Undervoltage dropout	90% of pickup	75%-98%	
Undervoltage pickup	90% of nominal	85%-100%	
Overvoltage dropout *	115% of nominal*	106%-135%	
Overvoltage pickup	95% of dropout	95%-100%	
Unbalance enable	Disable	Enable/Disable	
Unbalance dropout	20%	5%-20%	
Unbalance pickup	10%	3%-18%	
Voltage dropout time	0.5 sec.	0.1-9.9 sec.	
Underfrequency dropout	99% of pickup	95%-99%	
Underfrequency pickup	90% of nominal	80%-95%	
Overfrequency dropout	101% of pickup	101%-115%	
Overfrequency pickup	110% of nominal	105%-120%	
Frequency dropout time	Frequency dropout time 3 sec. 0.1-15 sec.		
* 690 volts, maximum. Default = 110% for 600 volt applications.			

Adjustable 1	ime Delay	/S	
Time Delay	Default	Adjustment Range	
Engine start, Source S2	3 sec.	0.0	
Engine start, Source S1 (gen/gen)	3 sec.	0-6 sec. †	
Engine cooldown, Source S2	5 min.		
Engine cooldown, S1 (gen/gen)	5 min.		
Fail to acquire standby source	1 min.		
Fail to acquire preferred source	1 min.	0-60 min.	
Transfer, preferred to standby	3 sec.		
Transfer, standby to preferred	15 min.		
Transfer, off to standby	1 sec.		
Transfer, off to preferred	1 sec.	1 sec 60 min.	
Fail to synchronize	60 sec.	10 sec - 15 min.	
Auto load test termination after transfer	1 sec.	1 sec60 min.	
Prime power run duration	6 min.	6 min 100 days (6 min. increments)	
Load Control Time Delays:			
Pretransfer to preferred	0 sec.		
Post-transfer to preferred	0 sec.		
Pretransfer to standby	0 sec.		
Post-transfer to standby	0 sec.	0-60 min.	
Load add Source1/Source2	0 sec.		
Load remove Source1/Source2	0 sec.		
Note: Time delays are adjustable in 1 second increments, except as			

**Note:** Time delays are adjustable in 1 second increments, except as noted.

‡ Engine start time delay can be extended to 60 minutes with an External Battery Supply Module Kit.

### Accessory Modules

The mounting kit holds up to five optional modules.

Module Current Draw Specifications, mA		
Alarm Module	75	
Standard I/O Module	75	
High Power I/O Module	100	
Maximum Total Current *	300	
* If an External Battery Module is installed, there is no current restriction.		

### Standard Input/Output Module

P	
Inputs	
Available Inputs	2
Input Definition	Contact closure
Current	5 mA Max
Connection Type	Terminal Strip
Wire Size	#14-24 AWG
Max Distance	700 feet
Outputs	
Outputs Available	6
Contact Type	Form C (SPDT)
Contact Voltage Rating	2 A @ 30 VDC
Contact voltage hatting	500 mA @ 125 VAC
Connection Type	Terminal Strip
Wire Size	#14-24 AWG

### High-Power Input/Output Module

Inputs		
Available Inputs	2	
Input Definition	Contact closure	
Current	5 mA Max	
Connection Type	Terminal Strip	
Wire Size	#14-24 AWG	
Max Distance	700 feet	
Outputs		
Outputs Available	3	
Contact Type	Form C (SPDT)	
Contact Voltage Rating	12 A @ 24 VDC 12 A @ 250 VAC 10 A @ 277 VAC 2 A @ 480 VAC	
Connection Type	Terminal Strip	
Wire Size	#14-24 AWG	
Environmental Specifications		
Temperature	-40°C to 85°C (-40°F to 185°F)	
Humidity	35% to 85% noncondensing	

### Alarm Module

- 90 dB Audible alarm
- Any alarm function can be programmed to trigger the audible alarm
- Chicago alarm function
- Preferred source selection
- Supervised transfer control (supervised transfer control switch required)
- Connection for external alarm

#### **External Alarm Connection Specifications**

=		
Wire Size	#12-22 AWG Cu	
	500 mA @ 120 VAC	
Contact Voltage Rating	250 mA @ 240 VAC	

#### External Battery Supply Module

- Energizes the ATS controls using an external battery when no source power is available
- Allows extended engine start time delays
- Allows the use of any combination of accessory modules (no current draw restriction, maximum of five modules total)
- Connects to one or two batteries, 12 VDC or 24 VDC system
- Current draw, 140 mA @ 12 VDC, 86 mA @ 24 VDC
- Provides low external battery voltage indication to the transfer switch controller
- Reverse-polarity protected

### **Other Controller Accessories**

Accessories are available either factory-installed or as loose kits, unless otherwise noted.

### Controller Disconnect Switch

- Disconnects power to controller without disconnecting load
- Mounts inside the enclosure

### Current Sensing Kit

Monitor current on all phases with 1% accuracy

### Digital Meter

- Measure and display voltage, current, frequency, and power for both sources
- Programmable visual alarms for high voltage, low voltage, and high current
- Three digital outputs
- Serial port for optional network connections
- Password-protected programming menus
- Joystick operation
- Factory-installed
- Joystick operation
- Available factory-installed
- For more information, see TT-1506, Digital Power Meters.

### Line-to-Neutral Voltage Monitoring

Monitors all line-to-neutral voltages

### Load Shed Kit

- Forced transfer from Emergency to OFF for programmed-transition models
- Customer-supplied signal (contact closure) is required for the forced transfer to OFF function
- Factory-installed only

### Padlockable User Interface Cover

- Provides additional protection against unauthorized access
- Standard on NEMA 3R enclosures

### RSA III Remote Serial Annunciator

- Monitors the generator set
- Monitors Normal and Emergency source status and connection
- Monitors ATS common alarm
- Allows remote testing of the ATS
- For more information about RSA III features and functions, see specification sheet G6-139.

### Supervised Transfer Control Switch

- Standard on models with non-automatic controls
- Optional for models with automatic controls
- Auto, manual, and transfer positions
- Automatic and non-automatic modes
- Alarm module required

Supervised Transfer Control Switch Operation for Automatic and Non-Automatic Transfer Switches			
Switch Position	Automatic Switches	Non-Automatic Switches	
AUTO	• Automatically transfers to the standby source, when available, if the preferred source is lost.		
	• Transfers back to the preferred source when it becomes available.		
MANUAL	<ul> <li>Automatically transfers to an available source if the connected source is lost.</li> </ul>	• Does not automatically transfer to an available source when the connected source is lost.	
	• Test, peak shave, and loaded exercise commands will transfer to the standby source.	• Test, peak shave, and loaded exercise commands are ignored.	
	• Does not automatically transfer back to preferred when both sources are available.	• Does not automatically transfer back to preferred when both sources are available.	
		<ul> <li>Transfers only when the switch is manually moved to the TRANSFER position as described below.</li> </ul>	
TRANSFER (momentary	• Does not initiate an engine start sequence. Generator set engine must be signalled to start by an event such as a loss of utility, loaded test, loaded exercise, etc.		
switch position)	<ul> <li>Allows transfer to the other source, if available. An event such as a loss of utility, loaded exercise, or loaded test must first initiate the transfer sequence.</li> </ul>		
	• Time delays will operate. Wait for time delays to expire, or press the End Time Delay button.		
	• Operates pre- and post-transfer load control time delays if both sources are available.		
	<ul> <li>MANUAL TRANSFER is displayed when the ATS is ready to transfer.</li> </ul>		

Environmental Specifications		
Operating Temperature	-20°C to 70°C (-4°F to 158°F)	
Storage Temperature	-40°C to 85°C (-40°F to 185°F)	
Humidity	5% to 95% noncondensing	

Main Board I/O Specifications		
Output contact type	Isolated form C (SPDT)	
Output contact rating	1 amp @ 30 VDC, 500 mA @120 VAC	
I/O terminals wire size	#12-24 AWG	

**DISTRIBUTED BY:** 

Availability is subject to change without notice. Kohler Co. reserves the right to change the design or specifications without notice and without any obligation or liability whatsoever. Contact your local Kohler® Power Systems distributor for availability.

© 2014 by Kohler Co. All rights reserved.